

REQUEST FOR QUOTES #2024-01
MEDIUM VOLTAGE TRANSFORMER
RESPONSE TO CLARIFYING QUESTIONS I
February 27, 2024

Please note that these are questions submitted by interested firms to this solicitation. The below answers are for clarification purposes only and in no way alter or amend the RFQ as published.

1. QUESTION: When would Oregon Tech like delivery of the transformer? This will help us know which manufacturer to offer, as their lead times vary.

ANSWER: Proposals should include anticipated delivery date. Oregon Tech would like delivery as soon as reasonably possible.

2. QUESTION: Please provide the ratios of the secondary CT's.

ANSWER: Secondary CT's are not required as the project currently has basic CT metering at the incoming feeders of the MDP.

3. QUESTION: Please provide more detailed information on secondary molded case circuit breaker requirements, technical breaker specs, etc. This requirement will extend the lead time somewhat.

ANSWER: Secondary molded case circuit breakers are not required at the transformer; main building switchgear "MDP" installed with main circuit breaker.

4. QUESTION: "Dark gray" is not a standard color. "Padmount Green" is a standard color. Would "Padmount Green" be acceptable? Alternatively, would "ANSI Gray" also be acceptable?

ANSWER: Standard manufacturer color "Padmount Green" is acceptable.

5. QUESTION: If aluminum windings have a shorter lead time, will Oregon Tech consider aluminum windings?

ANSWER: Copper windings are preferred. Proposal can include lead times for both copper and aluminum windings.

6. QUESTION: Please confirm the following for Secondary Switching/Overcurrent Protection:

Molded case circuit breaker:

KAIC

Voltage

Amperage
Type of overcurrent protection

ANSWER: Secondary molded case circuit breakers are not required at the transformer, main building switchgear “MDP” installed with main circuit breaker.

End of Clarifying Questions I